



1514 Schorr Pl, Bronx NY 10469 USA

Web: www.bedestimation.com

E-Mail: info@bedestimation.com

Project:

Location:

CLEINT

ARCHITECT

Name:

E-Mail:

Location:

SCOPE OF WORK

ADDENDA

Addendum Issued :

None


SPECIAL NOTES

BIDDER NAME: _____

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	MAT. COST	LAB. COST	EQUIP. COST	TOTAL COST
			010000	DIVISION 01 - GENERAL REQUIREMENTS						
1				MOBILIZATION	1	LS				
2				BOND & INSURANCE (See Spec. Sec. G01740)	1	LS				
3				PROJECT SUPERVISION & PROJECT MANAGEMENT	1	LS				
4				SUBMITTALS, SAMPLES, SHOP DRAWINGS, SITE SAFETY PLAN, ETC. (See Spec. Sec. S01300)	1	LS				
5				TEMPORARY FACILITIES & CONTROLS (See Spec. Sec. S01500)	1	LS				
6				PROJECT SCHEDULE (Primavera P3 or P6) See Spec. Sec. S01312	1	LS				
7				OFFICE OVERHEADS	1	LS				
8				CLOSEOUT PROCEDURES (See Spec. Sec. G01700)	1	LS				
9				PERMITS (DOT, DOB & After hour permits ETC.)	1	LS				
10		See cover and invitation to bid Pg. 10		(1) SECURITY GUARD (FOR 16 HOURS/DAY FOR 343 WEEKDAYS AND 24 HOURS/DAY FOR 137 WEEKENDS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. Performance Period 630 days Normal school hours 7:00AM to 4:40PM		HRS				
11				CUSTODIAL PERMIT (FOR 8 HOURS/PER DAY FOR 343 WEEKDAYS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. AFTER 150 DAYS HOLIDAYS AND OVERTIMES ARE EXCLUDED. Performance Period 630 days		HRS				
12				SCAFFOLDING.		SF				
13				SIDEWALK BRIDGE.		LF				
				Subtotal						
			060000	DIVISION 06 - Wood, Plastics And Composites						
				ROUGH CARPENTRY						
				POSTS						
14				6 x 6 Posts	23	FT				\$ -
15				8 x 6 Posts	231	FT				\$ -
16				10 x 6 Posts	15	FT				\$ -
17				8 x 8 Posts	35	FT				\$ -
				TRUSS						
18				PRE-ENGINEERED ROOF TRUSSES OVERFRAMING @24" O.C. NO. OF TRUSSES @1'-9" LENGTH: 1 NO. OF TRUSSES @8'-6" LENGTH: 1 NO. OF TRUSSES @15'-4" LENGTH: 1 NO. OF TRUSSES @22'-2" LENGTH: 1 NO. OF TRUSSES @29'-0" LENGTH: 1 NO. OF TRUSSES @35'-9" LENGTH: 1 NO. OF TRUSSES @42'-6" LENGTH: 1 NO. OF TRUSSES @49'-3" LENGTH: 2	254	LF				\$ -
				BEAMS						
19				3-1/2 x 11-7/8 PSL BEAM NO. OF BEAMS @8'-0" LENGTH: 2 NO. OF BEAMS @11'-0" LENGTH: 2 NO. OF BEAMS @13'-0" LENGTH: 1 NO. OF BEAMS @21'-9" LENGTH: 2	95	LF				\$ -
20				5-1/4 x 14 PSL BEAM NO. OF BEAMS @10'-10" LENGTH: 1	11	LF				\$ -
21				5-1/4 x 16 PSL BEAM NO. OF BEAMS @11'-9" LENGTH: 3 NO. OF BEAMS @16'-8" LENGTH: 1 NO. OF BEAMS @32'-9" LENGTH: 1	85	LF				\$ -
22				5-1/4 x 11-7/8 PSL BEAM NO. OF BEAMS @12'-3" LENGTH: 2	25	LF				\$ -
				JOISTS						
23				2x4 KATZ ROOF JOISTS @24" O.C. NO. OF JOISTS @2'-4" LENGTH: 58	135	LF				\$ -
24				11-7/8" TJI ROOF JOISTS @16" O.C. NO. OF JOISTS @41'-4" LENGTH: 26 NO. OF JOISTS @57'-11" LENGTH: 27	2638	LF				\$ -
25				16" TJI 560 ROOF JOISTS @12" O.C. NO. OF JOISTS @6'-9" LENGTH: 1 NO. OF JOISTS @12'-6" LENGTH: 1 NO. OF JOISTS @18'-3" LENGTH: 1 NO. OF JOISTS @24'-0" LENGTH: 1 NO. OF JOISTS @29'-9" LENGTH: 1 NO. OF JOISTS @32'-10" LENGTH: 4 NO. OF JOISTS @47'-9" LENGTH: 45	2371	LF				\$ -
				LEDGER						
26				P.T. 2 x 10 Ledger w/ (2) 3/4"dia. x 6" Hilti HDA-T w/ HY270 Adhesive @ 36" o.c.	365	LF				\$ -

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	MAT. COST	LAB. COST	EQUIP. COST	TOTAL COST
27				P.T. 2 x 4 w/ Hilti HY270 Adhesive At Bottom	198	LF				\$ -
				DECK						
28				Cant Wood Deck At Balconies	64	SF				\$ -
				SHEATHING						
29				3/4"thk. Plywood Subflooring w/ 10"dia. Nails @ 6" o.c.	2512	SF				\$ -
30				1/2"thk. Plywood Roof Sheathing w/ 10dia. Nails @ 6" o.c.	1160	SF				\$ -
31				1/2"thk. Plywood Wall Sheathing w/ #10 Screws @ 12" o.c.	2601	SF				\$ -
				STUDS						
32				2x4 WOOD STUDS @16" O.C. NO. OF STUDS @10'-0" HT: 82 NO. OF STUDS @11'-9" HT: 265 NO. OF STUDS @18'-0" HT: 166	6922	LF				
33				2x6 WOOD STUDS @16" O.C. NO. OF STUDS @11'-9" HT: 253 NO. OF STUDS @14'-6" HT: 36 NO. OF STUDS @18'-0" HT: 79	4917	LF				
				HANGERS						
34				BA Top Flange Hanger	447	EA				\$ -
35				LUS210	160	EA				\$ -
36				H2.5 Hurricane Tie	160	EA				\$ -
				BLOCKING						
37				Install Metal Strapping (Blocking) Within Rated Wall For Shelving	143	LF				\$ -
38				Blocking Provided For Mirrors	130	LF				\$ -
39				Blocking Provided For Grab Bars	39	LF				\$ -
40				Blocking Provided For Toilet Paper Holder	17	LF				\$ -
41				Blocking Provided For Sanitart Napkin Disposal	13	LF				\$ -
42				Blocking Provided For Baby Station	1	LF				\$ -
43				Fire Rated (3) 2 x 4 Wood Blocking For Mechanical Room Ladder	3	LF				\$ -
				FINISH CARPENTRY						
				EXAM ROOM						
44				WD-4: (1'8"W x 2'4"H) Glossy Laminate finish base cabinets - 1'8" x 2'4" x 1'1/2" = 8 LF - 1'6"W Adjustabel shelving	4	EA				\$ -
45				WD-4: (1'2"W x 3'7"H) Glossy Laminate finish upper cabinets - 1'2" x 3'7" x 1'8" = 7 LF - 12"W Double adjustabel shelving	4	EA				\$ -
46				WD-4: (1'2"W x 3'7"H) Glossy Laminate finish upper cabinets - 1'2" x 3'7" x 11" = 4 LF - 12"W Double adjustabel shelving	4	EA				\$ -
				LAB/ STORAGE ROOM						
47				WD-4: (2'2"W x 2'4"H) Glossy Laminate finish base cabinets - 1'8" x 2'4" x 1'6" = 12 LF - 2'0"W Adjustabel shelving	8	EA				\$ -
48				(1'4"W) Adjustable upper shelving	36	LF				\$ -
				SITTING DISPLAY CASE						
49				WD-1: Lacquer finish	4	SF				\$ -
50				WD-2: Lacquer finish	31	SF				\$ -
51				MT-2: 6" x 6" Metal shelving	9	LF				\$ -
52				MT-1: 4"H Metal base	9	LF				\$ -
				DISPLAY CABINETS						
				Type-1:						
53				(1'6"W x 10"H) Pull out drawer w/ heavy duty hardwares	39	LF				\$ -
54				(1'6"W x 4-1/4"H) Pull out drawer w/ heavy duty hardwares	117	LF				\$ -
55				WD-1: Lacquer finish	426	SF				\$ -
56				GL-1: 1'2" x 5" Clear glass display drawer	40	LF				\$ -
57				MT-2: 4"H Metal base	40	LF				\$ -
				Type-2:						
58				(1'6"W x 10"H) Pull out drawer w/ heavy duty hardwares	12	LF				\$ -
59				(1'6"W x 4-1/4"H) Pull out drawer w/ heavy duty hardwares	36	LF				\$ -
60				WD-1: Lacquer finish	131	SF				\$ -
61				8" x 5'6" Powder coated metal shelving	66	SF				\$ -
62				MT-2: 4"H Metal base	12	LF				\$ -
63				2'-11 1/4" x 5'6" Two leaf glass door	4	EA				\$ -
				Type-3:						

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	MAT. COST	LAB. COST	EQUIP. COST	TOTAL COST
64				(1'6"W x 10"H) Pull out drawer w/ heavy duty hardwares	4	LF				\$ -
65				(1'6"W x 4-1/4"H) Pull out drawer w/ heavy duty hardwares	11	LF				\$ -
66				WD-1: Lacquer finish	41	SF				\$ -
67				8" x 5'6" Powder coated metal shelving	28	SF				\$ -
68				MT-2: 4"H Metal base	5	LF				\$ -
				CABINETS						
69				2'-0"D Base Cabinet	522	LF				\$ -
70				1'-0"D x 3'-0"H Upper Cabinets	168	LF				\$ -
				INTERIOR TRIMS						
71				Interior Trim At Doors	16	LF				\$ -
72				Interior Trim At Windows	529	LF				\$ -
				Subtotal						\$0



**BID ESTIMATION
SERVICES**

