



1514 Schorr Pl, Bronx NY 10469 USA

Web: www.bedestimation.com

E-Mail: info@bedestimation.com

Project:

Location:

CLEINT

ARCHITECT

Name:

E-Mail:

Location:

SCOPE OF WORK

ADDENDA


Addendum Issued :

None

SPECIAL NOTES

BIDDER NAME: _____

| S# | DWG # | DETAIL # | CSI NO | DESCRIPTION | QTY. | UNIT | MAT. COST | LAB. COST | EQUIP. COST | TOTAL COST |
|----|-------|--|--------|---|-------|------|-----------|-----------|-------------|------------|
| | | | 010000 | DIVISION 01 - GENERAL REQUIREMENTS | | | | | | |
| 1 | | | | MOBILIZATION | 1 | LS | | | | |
| 2 | | | | BOND & INSURANCE (See Spec. Sec. G01740) | 1 | LS | | | | |
| 3 | | | | PROJECT SUPERVISION & PROJECT MANAGEMENT | 1 | LS | | | | |
| 4 | | | | SUBMITTALS, SAMPLES, SHOP DRAWINGS, SITE SAFETY PLAN, ETC. (See Spec. Sec. S01300) | 1 | LS | | | | |
| 5 | | | | TEMPORARY FACILITIES & CONTROLS (See Spec. Sec. S01500) | 1 | LS | | | | |
| 6 | | | | PROJECT SCHEDULE (Primavera P3 or P6) See Spec. Sec. S01312 | 1 | LS | | | | |
| 7 | | | | OFFICE OVERHEADS | 1 | LS | | | | |
| 8 | | | | CLOSEOUT PROCEDURES (See Spec. Sec. G01700) | 1 | LS | | | | |
| 9 | | | | PERMITS (DOT, DOB & After hour permits ETC.) | 1 | LS | | | | |
| 10 | | See cover and invitation to bid Pg. 10 | | (1) SECURITY GUARD (FOR 16 HOURS/DAY FOR 343 WEEKDAYS AND 24 HOURS/DAY FOR 137 WEEKENDS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. Performance Period 630 days Normal school hours 7:00AM to 4:40PM | | HRS | | | | |
| 11 | | | | CUSTODIAL PERMIT (FOR 8 HOURS/PER DAY FOR 343 WEEKDAYS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. AFTER 150 DAYS HOLIDAYS AND OVERTIMES ARE EXCLUDED. Performance Period 630 days | | HRS | | | | |
| 12 | | | | SCAFFOLDING. | | SF | | | | |
| 13 | | | | SIDEWALK BRIDGE. | | LF | | | | |
| | | | | Subtotal | | | | | | |
| | | | 050000 | DIVISION 05 - Metal | | | | | | |
| | | | | STRUCTURAL METAL | | | | | | |
| | | | | COLUMN | | | | | | |
| 14 | | | | W Steel Columns | 482 | LF | | | | |
| 15 | | | | 4" sq. Column | 220 | LF | | | | \$ - |
| | | | | COLUMN BASE PLATE | | | | | | |
| 16 | | | | Column Base Plates | 28 | EA | | | | \$ - |
| | | | | BEAMS | | | | | | |
| 17 | | | | Spandrel Beam Per Metal Bldg MFR | 130 | LF | | | | \$ - |
| 18 | | | | Moment Frame Beam Per Metal Bldg MFR | 645 | LF | | | | \$ - |
| | | | | PURLINS | | | | | | |
| 19 | | | | Roof Purlins @ 4'-6" o.c. | 4431 | LF | | | | \$ - |
| | | | | JOISTS | | | | | | |
| 20 | | | | 600S137-43 Joists @ 16" o.c. | 56 | LF | | | | \$ - |
| 21 | | | | 600S137-43 Joists @ 24" o.c. | 79 | LF | | | | \$ - |
| | | | | ROOF FRAMING | | | | | | |
| 22 | | | | Steel Ledger | 586 | FT | | | | \$ - |
| 23 | | | | Gage Metal Blocking | 360 | FT | | | | \$ - |
| 24 | | | | Bracing | 131 | FT | | | | \$ - |
| 25 | | | | Horizontal Z Girt | 360 | FT | | | | \$ - |
| 26 | | | | Steel Stubs | 126 | FT | | | | \$ - |
| 27 | | | | Channel Spanning | 694 | FT | | | | \$ - |
| 28 | | | | Aluminum AR-11 Ridge | 121 | FT | | | | \$ - |
| 29 | | | | 2" sq. Roof Purlins | 482 | FT | | | | \$ - |
| 30 | | | | Line Truss | 216 | FT | | | | \$ - |
| 31 | | | | 3/8" dia. 'X-Rods' | 2451 | FT | | | | \$ - |
| 32 | | | | Offset Gable Truss | 47 | FT | | | | \$ - |
| | | | | Floor Framing | | | | | | |
| 33 | | | | W18x50 (31LF) | 1569 | LBS | | | | \$ - |
| 34 | | | | W18x35 (87LF) | 3036 | LBS | | | | \$ - |
| 35 | | | | W18x40 (82LF) | 3299 | LBS | | | | \$ - |
| 36 | | | | W18x55 (56LF) | 3103 | LBS | | | | \$ - |
| 37 | | | | W 18x45 (45LF) | 2025 | LBS | | | | \$ - |
| | | | | DECK | | | | | | |
| 38 | | | | PMB Metal Deck | 19344 | SF | | | | \$ - |
| | | | | ORNAMENTAL METAL | | | | | | |
| | | | | EXTERIOR PANELS | | | | | | |
| 39 | | | | MP-1: Metal Panel Type: T10-A (Verti-Line) Color: Slate Grey (W38) Mfr: Metal Sales | 3187 | SF | | | | |

| S# | DWG # | DETAIL # | CSI NO | DESCRIPTION | QTY. | UNIT | MAT. COST | LAB. COST | EQUIP. COST | TOTAL COST | |
|----|-------|----------|--------|---|-----------------|------|-----------|-----------|-------------|------------|--|
| 40 | | | | MP-2: Metal Panel Type: T10-A (Verti-Line) Color: Old Town Grey (W25) Mfr: Metal Sales | 2877 | SF | | | | \$ - | |
| 41 | | | | MP-3: Metal Panel Type: T10-B Single Whthe (Verti-Line) Color: Slate Grey (W38) Mfr: Metal Sales | 804 | SF | | | | \$ - | |
| 42 | | | | MP-4: Metal Panel Type: TL-17 Flush Face Color: Slate Grey (W38) Mfr: Metal Sales | 77 | SF | | | | \$ - | |
| | | | |  | | | | | | | |
| | | | | BID ESTIMATION SERVICES | | | | | | | |
| | | | | RAILING | | | | | | | |
| 43 | | | | 3'-0"high Steel Pipe Handrail | 74 | LF | | | | \$ - | |
| | | | | FENCES | | | | | | | |
| 44 | | | | 6'-0"high Ameristar Steel Fencing Series: Montage PPP Style: Majestic Style w/ 3 Rail Panel System, Panels, 3" Spacing between 1" Pickets Finish: Black | 756 | LF | | | | \$ - | |
| 45 | | | | 8'-0"high Ameristar Steel Fencing Series: AEGIS II Style: Majestic Style w/ 3 Rail Panel System, Panels, 3" Spacing between 1" Pickets Finish: Black | 1138 | LF | | | | \$ - | |
| | | | | CURB | | | | | | | |
| 46 | | | | Steel Tube Curbs | 63 | LF | | | | \$ - | |
| | | | | | Subtotal | | | | | \$0 | |

