



1514 Schorr Pl, Bronx NY 10469 USA

Web: www.bedestimation.com

E-Mail: info@bedestimation.com

Project:

Location:

CLEINT

ARCHITECT

Name:

E-Mail:

Location:

SCOPE OF WORK

ADDENDA

Addendum Issued :

None

SPECIAL NOTES

BIDDER NAME: _____

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	MAT. COST	LAB. COST	EQUIP. COST	TOTAL COST
			010000	DIVISION 01 - GENERAL REQUIREMENTS						
1				MOBILIZATION	1	LS				
2				BOND & INSURANCE (See Spec. Sec. G01740)	1	LS				
3				PROJECT SUPERVISION & PROJECT MANAGEMENT	1	LS				
4				SUBMITTALS, SAMPLES, SHOP DRAWINGS, SITE SAFETY PLAN, ETC. (See Spec. Sec. S01300)	1	LS				
5				TEMPORARY FACILITIES & CONTROLS (See Spec. Sec. S01500)	1	LS				
6				PROJECT SCHEDULE (Primavera P3 or P6) See Spec. Sec. S01312	1	LS				
7				OFFICE OVERHEADS	1	LS				
8				CLOSEOUT PROCEDURES (See Spec. Sec. G01700)	1	LS				
9				PERMITS (DOT, DOB & After hour permits ETC.)	1	LS				
10		See cover and invitation to bid Pg. 10		(1) SECURITY GUARD (FOR 16 HOURS/DAY FOR 343 WEEKDAYS AND 24 HOURS/DAY FOR 137 WEEKENDS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. Performance Period 630 days Normal school hours 7:00AM to 4:40PM		HRS				
11				CUSTODIAL PERMIT (FOR 8 HOURS/PER DAY FOR 343 WEEKDAYS) EXCLUDED 150 DAYS FOR SUBMITTALS, APPROVAL AND PERMITS. AFTER 150 DAYS HOLIDAYS AND OVERTIMES ARE EXCLUDED. Performance Period 630 days		HRS				
12				SCAFFOLDING.		SF				
13				SIDEWALK BRIDGE.		LF				
				Subtotal						
			320000	DIVISION 32 - EXTERIOR IMPROVEMENTS						
				NEW WORK						
				MILLWORK AND CABINERY						
14				(12"D) Upper cabinet	18.08	FT				\$0
15				(24"D) Base cabinet	15.07	FT				\$0
16				(9 1/2"Dx18"H) Fixed HDPE pedestal bench	5	EA				\$0
17				Solid surface countertop w/ Backsplash	31.74	FT				\$0
18				(24"Wx18"Dx84"H) HDPE lockers	26	EA				\$0
19				(24"Dx18"H) Fixed HDPE pedestal bench against wall	4	EA				\$0
20				(12"Wx18"Dx84"H) HDPE lockers	10	EA				\$0
21				(24"Dx18"H) HDPE pedestal bench	2	EA				\$0
22				Raised rim, drop front 36"x36" MOP basin w/ SS wall guard	2	EA				\$0
23				(24"Wx18"Dx84"H) HDPE lockers	4	EA				\$0
				TOILET ACCESSORIES						
24				Full length mirror, 22"w x 65"h w/ 1/2" frame (no joints) w/bottom mounted at 9" aff	2	EA				\$0
25				mirror above counter, 22"w x 34"h w/ 1/2" frame (no joints) w/bottom mounted at 40" aff	7	EA				\$0
26				surface mounted paper towel dispenser	3	EA				\$0
27				semi-recessed paper towel dispenser / trash disposal combo	6	EA				\$0
28				surface mounted soap dispenser	10	EA				\$0
29				ss utility shelf w/ mop and broom holder	2	EA				\$0
30				surface / partition mounted toilet paper holder (jumbo)	8	EA				\$0
31				surface mounted sanitary napkin disposal	1	EA				\$0
32				Surface mounted towel pin	13	EA				\$0
33				36" grab bar	8	EA				\$0
34				42" grab bar	4	EA				\$0
35				18" vertical grab bar	6	EA				\$0
36				18" horizontal grab bar	2	EA				\$0
37				floor mounted, overhead braced toilet partitions	2	EA				\$0
38				24" deep wall hung urinal screen	1	EA				\$0
39				folding shower seat (top of seat to be at 17" min / 19" max aff and provide 250 lbs. Min load support)	2	EA				\$0
40				wall mounted shower head	8	EA				\$0
41				flexible hand held shower spray w/ 59" min length	2	EA				\$0
				Toilet compartments:						
42				Toilet compartments	6	EA				\$0
				SIGNAGES						
43				(8 1/2"x6") Type A1 signage	54	EA				\$0
44				(8 1/2"x12") Type B1 signage	1	EA				\$0
45				(8 1/2"x12") Type B2 signage	1	EA				\$0
46				(8 1/2"x12") Type B3 signage	2	EA				\$0
47				(12"x6") Type D2 signage	1	EA				\$0
48				(1"x6") Type D2 signage	1	EA				\$0
49				(8 1/2"x3") Type E1 signage	22	EA				\$0
50				(9"x9") Type E2 signage	3	EA				\$0
51				(1'3"x1'3") Type G2 signage	4	EA				\$0
52				(1'8"x8") Type J1 signage	17	EA				\$0
				Subtotal						\$0

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	MAT. COST	LAB. COST	EQUIP. COST	TOTAL COST

